

9. 区画線工

区画線工

1式

[illegible]

区画線集計表

		単位	実線・ゼブラ	実線・ゼブラ					摘 要
			白、W=15cm 溶融式	白、W=45cm 溶融式					
車道外側線	実線、白 W=15cm	m	898.8						
車道中央線	実線、白 W=15cm	m	60.4						
ゼブラ標示	実線、白 W=45cm	m		6.2					
停止線	実線、白 W=45cm	m		5.7					
合計		m	959	12					

区画線工 延長調書 (1)				
種 別	車道外側線 実線、白、W=15cm			
位 置	左・右	数 量	摘 要	
No. 0 + 0.000 ~ No. 8 + 0.000	左	164.0		
No. 8 + 0.000 ~ No. 13 + 0.000	左	100.2		
No. 13 + 0.000 ~ No. 19 + 17.810	左	139.4		
No. 20 + 1.200 ~ No. 22 + 14.030	左	49.0		
No. 0 + 4.590 ~ No. 8 + 0.000	右	158.4		
No. 8 + 0.000 ~ No. 13 + 0.000	右	100.4		
No. 13 + 0.000 ~ No. 20 + 0.000	右	140.5		
No. 20 + 0.000 ~ No. 22 + 9.560	右	46.9		
	計	m 898.8		

区画線工 延長調書 (2)				
種 別	車道中央線 (実線、白、W=15cm)			
位 置	左・右	数 量	摘 要	
No. 0 + 8.350 ~ No. 1 + 18.570		30.2		
No. 20 + 17.450 ~ No. 22 + 9.560		30.2		
	計	m 60.4		

区画線工 延長調書 (3)				
種 別	ゼブラ標示 (実線、白、W=45cm)			
位 置	左・右	数 量	摘 要	
No. 20 + 1.350 ~ No. 20 + 12.490	左	6.2		
	計	m 6.2		

区画線工 延長調書 (4)				
種 別	停止線 (実線、白、W=45cm)			
位 置	左・右	数 量	摘 要	
No. 0 + 8.350	右	2.8		
No. 22 + 7.680	左	2.9		
	計	m 5.7		