

数 量 総 括 表 (1 / 1)

工 種 ・ 種 別 ・ 細 別	規 格	単 位	数 量	摘 要
山本用水 施行延長		m	52.0	52.0
本工事				
漏水修繕工				
高圧洗浄工	30MPa	m ²	130	130.00
プライマー塗布（表面被覆工）		m ²	130	
表面被覆工（左官）	モルタル t=6mm	m ²	130	
不陸調整材	t=3mm	m ²	130	
目地充填工	1箇所/10.0m N=4箇所	m	12.5	12.5
土工				
人力土工	土砂撤去	m ³	2	2.1
残土処理 人力搬出 小規模	V=2.0+1.7=3.7m ³	m ³	4	3.8
仮設工				
排水ポンプ運転	常時排水 40～120m ³ /h 発動発電機	日	18	17.56
排水ポンプ設置撤去	1～5台	箇所	1	
土のう工	仕拵え・設置・撤去	m ³	2	1.7
単管傾斜足場工	A=7.5m×0.62=4.65	掛m ²	5	4.65
敷鉄板設置撤去工	N=4枚 A=3.0m×1.5m×4枚=18m ²	m ²	18	18

平 積 計 算 書

測 点	間 距	用水路(左壁)				用水路(右壁)				
		距 離	水路壁	平均壁高	平 積	距 離	水路壁	平均壁高	平 積	
No.0			0.85				0.85			
No.1	20.0	20.0	0.85	0.85	17.00	20.00	0.85	0.85	17.00	
No.2	20.0	20.0	0.85	0.85	17.00	20.00	0.85	0.85	17.00	
No.2+12.0	12.0	12.0	0.85	0.85	10.20	12.00	0.85	0.85	10.20	
計	52.00	52.00			44.20				44.20	

平 積 計 算 書

測 点	間 距	用水路(床面)								
		距 離	水路幅	平均幅	平 積					
No.0			0.80							
No.1	20.00	20.00	0.80	0.80	16.00					
No.2	20.00	20.00	0.80	0.80	16.00					
No.2+12.0	12.00	12.00	0.80	0.80	9.60					
計		52.00			41.60				0.0	